


PROPOSED EQUIPMENT PLAN

SCALE: 1/2"=1' FOR 11"x17"
1"=1' FOR 22"x34"



NOTES:

1. NORTH ARROW SHOWN AS APPROXIMATE.
2. SOME EXISTING AND PROPOSED INFORMATION NOT SHOWN FOR CLARITY.
3. PLAN BASED ON OBSERVATIONS MADE DURING SITE VISIT BY DEWBERRY ENGINEERS INC. ON 07-31-14 AND BUILDING PLANS PROVIDED BY THE PLYMOUTH CONG. CHURCH.
4. PROPOSED EQUIPMENT TO BE INSTALLED PER STRUCTURAL ANALYSIS BY DEWBERRY ENGINEERS INC. DATED 10-12-15.
5. PROPOSED FIXED LADDER TO BE INSTALLED PER MANUFACTURER SPECIFICATIONS.
6. PROPOSED LADDER & GATE MAKE & MODEL SHALL BE APPROVED BY VZW CM & LL. EXISTING LADDER SHALL BE SALVAGED AND PROVIDED TO LL.
7. ALL PROPOSED EQUIPMENT SHALL NOT BE MOUNTED OVER OR NEAR EXISTING FLASHING OR REPAIR AREAS. ADJUST EQUIPMENT OR SUPPORT ANCHORS AS NECESSARY.
8. NOISE REDUCTION METHODS ARE NOT DESIGNED TO MEET A SPECIFIC SOUND LEVEL AND ARE FOR GENERAL NOISE REDUCTION ONLY.
9. LOCATION & QUANTITY OF PROPOSED LIGHTING SHALL BE APPROVED BY VZW CM & LL. LIGHTING SHALL PROVIDE ADEQUATE COVERAGE TO BE ABLE TO MANEUVER AROUND ENTIRE SPACE. LOCATE LIGHT SWITCH WITH DIRECTION BY VZW CM & LL.

CONSTRUCTION NOTES:

1. EXISTING FLOOR STRUCTURE AND STEEPLE REINFORCED OR SHORED IF AREA IS TO BE SIGNIFICANT WEIGHT WILL NEED TO BE SUPPORTED BY WORKERS, ETC.) ALL MEANS AND METHODS TO BE RESPONSIBILITY OF THE CONTRACTOR. RECOMMENDATIONS DURING CONSTRUCTION.
2. ALL PROPOSED WORK WITHIN STEEPLE TO THE STEEPLE REPAIRS BY OTHERS, AS REPORT ISSUED BY RENE MUGNIER ASSOCIATES 08-27-14, ARE COMPLETED.